12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for restoring Cheluvanahalli Hirekere, Register No. 121 of Arsikere Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
	I. Bund.				
1	Silt clearing in breached portion	C.yd.	0 2 0	844	
2	Earthwork excavation for clay puddle wall ..	,,	0 3 0	71	
3	Cutting grips and steps at sides of breaches ..	L.S.	20 0 0		
4	Size stones in surki mortar masonry ..	C.ft.	0 5 6	848	
5	Raising clay puddle wall including watering and consolidation in layers and lead ..	C.yd.	0 12 0	159	
6	Cutting and removing trees and thick jungles on the old bund	L.S.	50 0 0		
7	Cutting grips on slopes of old bund	Grade	2 0 0	22	
8	Earthwork to bund including watering and consolidation	C.yd.	0 4 0	2,165	
	(*a*) Using old earth with watering and consolidation	,,	0 1 0	1,023	
9	Gravel backing to revetment	,,	0 8 0	90	
10	Rough stone work new including jelly packing and chips wedging	,,	1 12 0	72·36	
11	Resetting old stone revetment	,,	1 0 0	120	
12	Turfing the slopes	S.yd.	0 0 11	2,501	
13	Providing and fixing new grade stones, including chiselling, figures and painting, etc., complete	No.	2 8 0	23	
14	Providing and fixing new Index stones ..	,,	0 12 0	23	
15	Providing and fixing new B.M.stones, including chiselling and painting, etc., complete ..	,,	3 0 0	2	
16	Providing and fixing Reg. No. stone ..	Each	4 0 0	1	
	II. Constructing a weir 85' long crest at 50·00.				
1	Earthwork excavation	C.yd.	0 3 0	762	
2	Stone jelly in surki mortar concrete	C.ft.	0 4 6	420	
3	Size stones in surki mortar	,,	0 5 6	551	
4	Burnt stone slabs 6" thick dressed, including fixing with joggle joints	S.ft.	0 8 0	316	
5	(*a*) Rough stone work new including jelly packing and chips wedging	C.yd.	1 12 0	202	
	(*b*) Old stone work with new jelly	,,	0 12 0	12	
6	Boulder filling to scoured portions below the weir in right flank end	,,	1 0 0	33	
7	Cement pointing	Sqr.	4 0 0	5	
8	Draft and approach clearing	L.S.	20 0 0		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE SUPERINTENDENT, GOVERNMENT GARDENS, BANGALORE.

Abstract Notification, dated 22nd June 1937.

The attention of the public is invited to the detail Notification, calling for tenders for the supply of contingent articles, Hardware and Miscellaneous articles, etc., etc., required for the use of the office of the Curator, Parks and Gardens, Mysore, during 1937-38, published in pages 1049-1053, Part VI of the *Mysore Gazette*, dated 1st July 1937.

The last date for receiving tenders is 12th July 1937.

L. S. DORASAMI,
Offg. *Superintendent.*